

**LEGEND:**

	EXISTING CONTOUR
	N/F
	UTILITY POLE
	BORDERING VEGETATED WETLAND
	100' BUFFER ZONE
	APPROX. EXISTING OVERHEAD WIRES
	APPROX. EXISTING WATER MAIN
	APPROX. EXISTING GAS SERVICE
	EXISTING TREELINE
	PROPOSED TREELINE
	PROPOSED CONTOUR
	PROPOSED SPOT GRADE
	DMH
	CB
	SMH
	PROPOSED UNDERGROUND UTILS
	PROPOSED GAS LINE
	PROPOSED WATER LINE
	FLARED END
	DROP INLET
	INLINE DRAIN
	TRENCH DRAIN

- GENERAL NOTES**
1. ALL UNDERGROUND UTILITIES SHOWN HEREON WERE COMPILED ACCORDING TO AVAILABLE RECORD PLANS FROM VARIOUS UTILITY COMPANIES AND PUBLIC AGENCIES AND ARE APPROXIMATE ONLY. ACTUAL LOCATIONS MUST BE DETERMINED IN THE FIELD BEFORE EXCAVATING, BLASTING, INSTALLING, BACKFILLING, GRADING, PAVEMENT RESTORATION OR REPAIRING. ALL UTILITY COMPANIES, PUBLIC AND PRIVATE, MUST BE CONTACTED INCLUDING THOSE IN CONTROL OF UTILITIES NOT SHOWN ON THIS PLAN. SEE CHAPTER 370, ACTS OF 1963 MASS. WE ASSUME NO RESPONSIBILITY FOR DAMAGE INCURRED AS A RESULT OF UTILITIES OMITTED OR INACCURATELY SHOWN. BEFORE PLANNING FUTURE CONNECTIONS, THE APPROPRIATE PUBLIC UTILITY ENGINEERING DEPARTMENT MUST BE CONSULTED. DIG-SAFE TEE. NO. (888) 344-7233.
  2. UNLESS OTHERWISE SPECIFIED ON THESE PLANS, ALL CONSTRUCTION METHODS AND MATERIALS SHALL COMPLY WITH SPECIFICATIONS OUTLINED IN THE ACTON ZONING BYLAW.
  3. ALL LIMITS OF WORK SHALL BE LOCATED IN THE FIELD PRIOR TO CONSTRUCTION OR SITE CLEARING.
  4. ALL WATER PIPES, HYDRANTS, GATE VALVES AND OTHER APPURTENANCES SHALL BE INSTALLED IN ACCORDANCE WITH THE ACTON WATER SUPPLY DISTRICT REQUIREMENTS.
  5. ALL STUMPS AND OTHER CONSTRUCTION DEBRIS SHALL BE PROPERLY REMOVED ANY FILL MATERIAL USED SHALL BE FREE OF HAZARDOUS MATERIALS OR WASTE.
  6. ALL DRAIN PIPES SHALL BE ADS N-12 UNLESS OTHERWISE SHOWN.
  7. TRANSPORTATION OF FILL, EARTH, OR CONSTRUCTION DEBRIS TO OR FROM THE SITE SHALL BE RESTRICTED TO DAYTIME HOURS (9 AM TO 4 PM) MONDAY THROUGH FRIDAY.
  8. ANY FILL MATERIAL USED SHALL BE FREE OF HAZARDOUS MATERIALS OR WASTE.
  9. COMBINATION OF CURBING, RETAINING WALLS, AND STONE WALLS ALONG PROPOSED DRIVEWAY, AROUND PROPOSED CONSTRUCTED STORMWATER WETLANDS, AND WETLAND REPLICATION AREA TO BE DESIGNED BY A STRUCTURAL ENGINEER. PLANS TO BE SUBMITTED TO CONSERVATION COMMISSION PRIOR TO CONSTRUCTION.

**NONSET PATH  
WETLAND PERMITTING PLAN  
ACTON, MASSACHUSETTS**

GRADING, DRAINAGE & UTILITIES PLAN  
FOR:  
HAWTHORNE HOMES, LLC  
SCALE: 1"=20' JANUARY 26, 2011  
REV. JUNE 28, 2011




















**STAMSKI AND McNARY, INC.**  
1000 MAIN STREET ACTON, MASSACHUSETTS  
(978) 263-8585  
ENGINEERING - PLANNING - SURVEYING

0 10 20 40 60 80 FT

(4627CONCEPT3D.DWG) SHEET 1 OF 3 SM-4627


JOSEPH  
MARCH  
CIVIL  
#840472  
REGISTERED PROFESSIONAL ENGINEER

WILLIAM  
F.  
McNARY  
No. 30753  
REGISTERED PROFESSIONAL LAND SURVEYOR



**ADS END SECTION DIMENSIONS**

PIPE DIAMETER	PART NO.	DIMENSION (inches)				
		A(±)	B MAX	H(1±)	L(1/2±)	W(2±)
12" and 15"	1210 NP	6.5	10	6.5	25	29
18"	1810 NP	7.5	15	6.5	32	35
24"	2410 NP	7.5	18	6.5	36	45
36"	3610 NP	10.5	NA	7.0	53	68



**NONSET PATH WETLAND PERMITTING PLAN**  
**ACTON, MASSACHUSETTS**


**DETAILS**



FOR: **HAWTHORNE HOMES, LLC**  
SCALE: 1"=20'  
JANUARY 26, 2011  
REV. JUNE 28, 2011

**STAMSKI AND McNARY, INC.**  
1000 MAIN STREET ACTON, MASSACHUSETTS  
(978) 263-8585  
ENGINEERING - PLANNING - SURVEYING

0 10 20 40 60 80 FT


(4627CONCEPT3D.DWG) SHEET 2 OF 3 SM-4627





PLANT LIST

Symbol	Botanical Name	Common Name	Size	Quantity	Condition
Wetland Replication Area					
TREES					
AR	<i>Acer rubrum</i>	Red Maple	1.0" caliper	5	B & B
SHRUBS					
VC	<i>Vaccinium corymbosum</i>	Highbush Blueberry	36 inch	9	CONT. GROWN
IV	<i>Ilex verticillata</i>	Winterberry	36 inch	20	CONT. GROWN
AV	<i>Azalea viscosum</i>	Swamp Azalea	36 inch	5	CONT. GROWN
VD	<i>Viburnum dentatum</i>	Arrowwood	36 inch	7	CONT. GROWN
CA	<i>Cornus amomum</i>	Silky Dogwood	36 inch	6	CONT. GROWN
FERNS					
OC	<i>Osmunda cinnamomea</i>	Cinnamon Fern	Gallon	30	CONT. GROWN
OS	<i>Onoclea sensibilis</i>	Sensitive Fern	Gallon	20	CONT. GROWN
OR	<i>Osmunda regalis</i>	Royal Fern	Gallon	9	CONT. GROWN



**CONSTRUCTION SEQUENCE FOR WETLAND CROSSING**

- INSTALL EROSION CONTROL BARRIER PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION AT ALL LOCATIONS SHOWN ON THE PLANS. SET HAYBALES LINES IN THE LOCATIONS SPECIFIED BY THE DESIGN ENGINEER.
- NOTIFY CONSERVATION COMMISSION 48 HOURS PRIOR TO STARTING DATE OF CONSTRUCTION.
- CLEAR AND GRUB AREA WITHIN WETLAND CROSSING AND DESIGNATED AREA FOR WETLAND REPLICATION.
- EXCAVATE MATERIAL WITHIN WETLAND REPLICATION AREA TO ONE (1) FOOT BELOW GRADES SHOWN ON PLAN. STOCKPILE EXCAVATED MATERIAL OUTSIDE OF THE 100' BUFFER ZONE.
- STRIP ORGANIC MATERIAL FROM AREA WITHIN WETLAND CROSSING AND SPREAD EXCAVATED ORGANIC MATERIAL OVER WETLAND REPLICATION AREA TO THE GRADES SHOWN ON THE PLAN. COMPLETE WETLAND REPLICATION AREA IN COMPLIANCE WITH "CONSTRUCTION SEQUENCE FOR WETLAND REPLICATION AREA".
- INSTALL SEWER MAIN, ELECTRICAL, AND FIRE ALARM.
- INSTALL GAS LINE.
- INSTALL HEADWALLS AND CULVERT.
- PLACE AND COMPACT GRAVEL FILL FOR PROPOSED DRIVEWAY WITHIN WETLAND CROSSING TO THE GRADES SHOWN ON THE PLAN.
- STABILIZE SLOPES IN WETLAND FILL AREA WITH 6" OF LOAM AND HYDROSEEDING.
- INSTALL OTHER PROPOSED UNDERGROUND UTILITIES.
- INSTALL DRIVEWAY SURFACE TO THE WIDTH SHOWN ON THE PLAN.
- LOAM AND SEED ALL DISTURBED SURFACES WHICH HAVE NOT BEEN STABILIZED.
- REMOVE EROSION CONTROL BARRIERS AFTER ALL VEGETATION IS ESTABLISHED AND THE APPROVING AUTHORITY HAS ISSUED A CERTIFICATE OF COMPLIANCE.

**Proposed Wetland Replication Area**


The proposed wetland replication area is currently vegetated by a White Pine stand. All of the vegetation will have to be removed in order to construct the replication area. This will result in the removal of the following trees:

- 8 White Pines *Pinus strobus*
- 1 Red Oak *Quercus rubra*
- 1 White Oak *Quercus alba*
- 4 small Black Birch *Betula lenta*

There are very few shrubs and the herbaceous layer consists of an escaped groundcover.

- Before planting the replication area, the Applicant shall remove any trees, shrubs, stumps, and sod from the replication area. These are not to be stockpiled in the resource area or buffer zones while awaiting disposition.
- During the removal of the trees, shrubs, stumps and sod, some of the soils (within the replication area) will likely be removed during the process. Additional wetland soils shall be provided in quantities sufficient to establish grades as shown on the previously referenced plans. The replacement soil shall be purchased by the Applicant at a 1:1 mix of loam to peat/organic soils.
- The replication area shall be excavated to a depth of 8 to 12 inches below proposed finish grades. The replication area is to then be backfilled with the 1:1 mixture of loam to peat/organic soil.
- The wetland soils shall be deposited in the replication area in a manner minimizing travel and subsequent compaction of the underlying material and replacement wetland soils.
- The replication area shall not have finished grading which results in a completely flat topography. The finish grading should result in a shallow pit and mound topography throughout the replication area.
- Any fill not being utilized, must be stockpiled outside the resource area and buffer zones. Precautions shall be taken as necessary to prevent erosion of the stockpiled material.
- Any significant field changes deemed necessary to achieve final grading within twelve inches from the groundwater table, must be approved by the Botanist (in the field) and reported to the Conservation Commission in the weekly report.
- Upon completion of the replication area, siltation fence shall be placed around the entire perimeter (of the replication area) to protect the replication area during the remainder of construction.
- After replication construction is completed, no fertilizer, limestone, superphosphate, mulch or other amendments shall be added to the wetland soils.

**CONSTRUCTED STORMWATER WETLAND**  
SCALE: 1" = 40'



**CONSTRUCTED STORMWATER WETLAND**  
SCALE: 1" = 40'

- All plants dug for reuse shall be immediately moved to a protective storage area approved by the Botanist. Plants shall be set plumb on grade or in prepared holes and guyed as necessary. The area or holes shall be backfilled with suitable topsoil to cover the rootballs entirely and mulched to prevent erosion. All stored vegetation shall be maintained in a damp condition by regular watering. All horticultural measures required for the survival of collected plantings shall be utilized by the Applicant.
- After the replication area has been constructed, stockpiled plants shall be replanted in locations specified and approved by the Botanist.

**WETLAND REPLICATION SCHEDULE**

**Part 1 General**

- 1.01 Extent of Work
  - The work includes the furnishing of all plant, labor, equipment, materials and required professional services in connection with the protection, replication and provision of specific mitigation and enhancement measures to minimize and compensate for impacts to wetlands.
  - It shall be the responsibility of the Applicant to retain a Botanist, Biologist, Wetland Scientist or other individual with qualifications and a minimum of five years experience in similar wetland replications, and thoroughly versed in the Commonwealth of Massachusetts Wetlands Protection Act (MGL Chapter 131, section 40) and all other relevant regulations of the Department of Environmental Protection. This individual, herein after referred to as "Botanist", shall be approved by the Town of Acton Conservation Commission.

**Part 2 Execution**

**2.01 General**

- The Applicant shall plan and execute operations in a manner minimizing the amount of excavated and exposed fill, or other foreign materials that may be washed or otherwise carried into the replication area.

**2.02 Erosion/Sedimentation Control**

- The applicant shall install hay bales and/or siltation fencing and utilize erosion/sedimentation control methods prior to the commencement of any work.

**2.03 Replication Area Preparation**

- This wetland replication shall be performed under the direction and guidance of a qualified Botanist and as specified herein.

- The replication area shall have finished grades which meet the existing grades in the adjacent wetland as shown on this plan.

- Before planting the replication area, the Applicant shall remove any trees, shrubs, stumps, and sod from the replication area. These are not to be stockpiled in the resource area or buffer zones while awaiting disposition.

- During the removal of the trees, shrubs, stumps and sod, some of the soils (within the replication area) will likely be removed during the process. Additional wetland soils shall be provided in quantities sufficient to establish grades as shown on the previously referenced plans. The replacement soil shall be purchased by the Applicant at a 1:1 mix of loam to peat/organic soils.

- The replication area shall be excavated to a depth of 8 to 12 inches below proposed finish grades. The replication area is to then be backfilled with the 1:1 mixture of loam to peat/organic soil.

- The wetland soils shall be deposited in the replication area in a manner minimizing travel and subsequent compaction of the underlying material and replacement wetland soils.

- The replication area shall not have finished grading which results in a completely flat topography. The finish grading should result in a shallow pit and mound topography throughout the replication area.

- Any fill not being utilized, must be stockpiled outside the resource area and buffer zones. Precautions shall be taken as necessary to prevent erosion of the stockpiled material.

- Any significant field changes deemed necessary to achieve final grading within twelve inches from the groundwater table, must be approved by the Botanist (in the field) and reported to the Conservation Commission in the weekly report.

- Upon completion of the replication area, siltation fence shall be placed around the entire perimeter (of the replication area) to protect the replication area during the remainder of construction.

- After replication construction is completed, no fertilizer, limestone, superphosphate, mulch or other amendments shall be added to the wetland soils.

**Part 3 Removing, Storing, and Replanting of Existing Wetland Trees and Shrubs**

- In any disturbed wetland (where practical), the Applicant may, at his option, dig up, store and maintain existing wetland trees and shrubs for use in the replication area. Trees shall be a minimum of one inch caliper and shrubs shall be thirty-six inches in spread or height. All plants shall be vigorous and well formed specimens. All plant materials dug for this purpose shall be dug by hand, hydraulic tree spade specifically designed for this purpose or other suitable equipment of sufficient size to remove the rootball. Rootball size shall be the minimum specified by the American Association of Nurserymen for each species. For hand dug plants, a suitable burlap or other wrap or container shall be provided to keep the rootball intact.

- All plants dug for reuse shall be immediately moved to a protective storage area approved by the Botanist. Plants shall be set plumb on grade or in prepared holes and guyed as necessary. The area or holes shall be backfilled with suitable topsoil to cover the rootballs entirely and mulched to prevent erosion. All stored vegetation shall be maintained in a damp condition by regular watering. All horticultural measures required for the survival of collected plantings shall be utilized by the Applicant.

- After the replication area has been constructed, stockpiled plants shall be replanted in locations specified and approved by the Botanist.

**Part 4 Wetland Replication Planting**

**A. Wetland planting shall be performed between March 1 and October 15 or as recommended by the Botanist.**

- Wetland plantings shall consist of a minimum of five trees planted no farther apart than twenty-five feet on center and forty-seven shrubs planted no farther apart than eight feet on center.

- The tree layer will be comprised of five Red Maple (*Acer rubrum*).

- Shrubs shall consist of twenty Winterberry (*Ilex verticillata*), nine Highbush Blueberry (*Vaccinium corymbosum*), seven Arrowwood (*Viburnum dentatum*), six Silky Dogwood (*Cornus amomum*) and five Swamp Azalea (*Azalea viscosum*).

- The herbaceous layer shall include thirty Cinnamon Ferns (*Osmunda cinnamomea*), twenty Sensitive Ferns (*Onoclea sensibilis*) and nine Royal Ferns (*Osmunda regalis*).

- The Applicant shall have the option of digging, storing and replanting existing trees and shrubs per Part 3 of this Schedule, or alternatively, providing and planting new wetland species, purchased by the Applicant from nursery stock, and approved by the Botanist.

- Wetland planting, in the replication area, will be performed in a manner which reproduces the placement and proportions of the plant species that are found in the adjacent wetland resource area.

- All wetland plantings will be performed by hand. Burlap will be removed from the top third of the rootballs and ropes, twine and wire baskets will be completely removed from the rootballs. Completely remove all plastic burlap, rope, twine and wire baskets from the replication area. Completely remove the containers from the potted plants while keeping the soil around the roots unbroken.

- After plantings are completed, the replication area shall be hand raked to eliminate any depressions, greater than four inches in depth, which may be created during digging and to eliminate compaction of the soils as much as possible.

- Once planting is completed, the remaining exposed soils maybe over-seeded with New England Wetmix at the discretion of the Botanist.

- The intent of this schedule is to insure that at least 75 percent of the replication surface area is re-established with indigenous wetland plant species within two growing seasons of their planting, in accordance with the Massachusetts DEP Wetlands Protection Act regulations. Purple Loosestrife (*Lythrum salicaria*) and European Buckthorn (*Rhamnus frangula*) shall not be planted in the replication area. If after 180 growing season days, it is evident in the opinion of the Botanist that it is unlikely that the 75 percent re-establishment requirement will be achieved, the Applicant shall supplement the plantings as necessary to achieve the required coverage. If after the end of two growing seasons, 75 percent re-establishment has not been achieved, the Applicant shall provide and plant healthy wetland vegetation in sufficient quantities to achieve the 75 percent re-establishment.

**Part 5 Wetland Replication Monitoring**

- The Town of Acton Conservation Commission will be notified 72 hours in advance of the commencement of the wetland replication construction.

- All construction activities and plantings will be overseen by a qualified Botanist.

- A brief progress report will be provided to the Town of Acton Conservation Commission at the end of each week until construction and planting of the replication area has been completed.

- Two reports will be provided to the Town of Acton Conservation Commission. The reports will be provided on June 1st and October 1st following the planting of the replication area. These reports will be provided for two growing seasons.

- Each report will include an observed species list, relative abundance of each species, percent cover of upland and wetland species, the viability of the plantings and proposed remedial measures to ensure 75 percent re-establishment within two growing seasons. Pictures shall also be provided.

- While performing the inspection of the replication area, any invasive plants species found shall be removed. The plant species, and number of plants removed, shall be included within the monitoring reports.

- If the replication area does not achieve the required 75 percent coverage within two growing seasons, then additional plantings will be provided as per Part 4 section G. These plantings will be monitored for the next two growing seasons with reports provided to the Town of Acton Conservation Commission on June 1st and October 1st of each year in order to ensure the viability of these late plantings.

**NONSET PATH  
WETLAND PERMITTING PLAN  
ACTON, MASSACHUSETTS**

**DETAILS**  
FOR: HAWTHORNE HOMES, LLC  
SCALE: 1"=20' JANUARY 26, 2011  
REV. JUNE 28, 2011

**STAMSKI AND McNARY, INC.**  
1000 MAIN STREET ACTON, MASSACHUSETTS  
(978) 263-8585  
ENGINEERING - PLANNING - SURVEYING  
0 10 20 40 60 80 FT  
(4627CONCEPT3D.DWG) SHEET 3 OF 3 SM-4627

