

<u>ITEM 450.90</u>	<u>Contractor Quality Control</u>	<u>Ton (Megagram)</u>
<u>ITEM 452.</u>	<u>Asphalt Emulsion for Tack Coat</u>	<u>Gallon (Liter)</u>
<u>ITEM 453.</u>	<u>HMA Joint Sealant</u>	<u>Foot (Meter)</u>
<u>ITEM 455.22</u>	<u>SUPERPAVE Surface Course - 9.5 (SSC - 9.5)</u>	<u>Ton (Megagram)</u>
<u>ITEM 455.31</u>	<u>SUPERPAVE Intermediate Course - 12.5 (SIC - 12.5)</u>	<u>Ton (Megagram)</u>

Work under these Items shall conform to the relevant provisions of Document 00717 SUPERPAVE REQUIREMENTS contained herein and the following:

The Equivalent Single Axle Loads (ESALs) for the design travel lane over a 20-year period, is  $\leq 0.3$  Million 18-kip (80-kn) ESALs. The PGAB Grade selected for this Contract is **PG 64-28**

Note: The hot mix asphalt (HMA) Walks and Drives with Superpave HMA mixtures shall be paved in accordance with Section 701 of the Standard Specification which shall be the basis for the work and paid for under Item 702. HMA Walks and Item 703. HMA Drives. The Superpave HMA for Items 702. And 703. shall not be subject to QA sampling and testing.