


TEST PIT DATA:

DATE OF TESTING: 12/4/12 1/3/13
 TEST BY: STAMSKI AND McNARY, INC.
 CERT. SOIL EVAL.: BENJAMIN EWING 2005
 WITNESSED BY: EVAN CARLONI




PERC. TEST DATA:


DATE OF TESTING: 10/9/12
 TEST BY: STAMSKI AND McNARY, INC.
 CERT. SOIL EVAL.: BILL HALL, 2012
 WITNESSED BY: EVAN CARLONI

PT-12-A
 DEPTH OF TEST: 42"
 RATE: 24 MPI


PT-12-B
 DEPTH OF TEST: 44"
 RATE: 28 MPI




D.BOX DETAIL:



SOIL ABSORPTION SYSTEM:




LOCUS PLAN:







NOTES:

- THIS PLAN IS FOR THE DESIGN AND CONSTRUCTION OF A SEWAGE DISPOSAL FACILITY ONLY.
- ALL CONSTRUCTION METHODS AND MATERIALS SHALL CONFORM TO TITLE 5 AND THE ACTON BOARD OF HEALTH REGULATIONS.
- IF ALTERATIONS (REMOVAL OF VEGETATION, GRADING, EXCAVATIONS, ETC.) ARE TO BE MADE WITHIN 100 FT OF WETLAND AREAS (PONDS, BROOKS, SWAMPS, ETC.) A REQUEST FOR DETERMINATION OF APPLICABILITY OF THE WETLANDS PROTECTION ACT (c131 s40A) SHOULD BE FILED WITH THE TOWN'S CONSERVATION COMMISSION. THE FILING OF A NOTICE OF INTENT MAY BE REQUIRED AND LOCAL BYLAWS MAY APPLY.
- ACCEPTABLE MATERIAL SPECIFICATIONS FOR DISTRIBUTION LINES: PVC-SCHEDULE 40 (ASTM D 1785 & D 2665), SDR 35 (ASTM D 3034), ABS-SCHEDULE 40 (ASTM F 628), HDPE-SHALL MEET OR EXCEED ASTM F 810 FOR SMOOTH WALL POLYETHYLENE PIPE FOR USE IN DRAINAGE AND WASTE DISPOSAL FIELDS. SCHEDULE 40 PVC SHALL BE USED IN AREAS SUBJECT TO VEHICULAR TRAFFIC.
- UNLESS OTHERWISE SHOWN, THERE ARE NO KNOWN WELLS WITHIN 150' OF THE PROPOSED SEWAGE DISPOSAL SYSTEM.
- ALL TOP, SUBSOIL, FILL, BOULDERS, AND OTHER MATERIALS UNDER AND WITHIN 5' OF THE PROPOSED LEACHING AREA SHALL BE REMOVED AND REPLACED WITH SUITABLE MATERIAL ACCORDING TO TITLE V(2006) SECTION 15.255 "CONSTRUCTION IN FILL"
- PER TITLE 5 REQUIREMENTS, THE DESIGN ENGINEER IS REQUIRED TO INSPECT CONSTRUCTION OF THE SEPTIC SYSTEM AND CERTIFY THAT THE SYSTEM IS CONSTRUCTED ACCORDING TO THE PLANS, LOCAL REGULATIONS, AND TITLE 5. IN MOST INSTANCES THE DESIGN ENGINEER IS ALSO REQUIRED TO PREPARE AN "AS-BUILT" PLAN. UNLESS OTHERWISE SPECIFICALLY STATED IN WRITING BETWEEN OWNER AND THE INSTALLER, THE INSTALLER SHALL BE RESPONSIBLE FOR COORDINATING INSPECTIONS WITH THE DESIGN ENGINEER AND PAY FOR THESE SERVICES. NOTIFYING THE DESIGN ENGINEER DOES NOT RELIEVE THE OWNER OR INSTALLER FROM THE RESPONSIBILITY OF HAVING THE REQUIRED INSPECTIONS ETC. BY THE BOARD OF HEALTH.
- FINISHED GRADE OVER THE LEACHING AREA SHALL HAVE A MINIMUM SLOPE OF 2%.
- THE FIRST TWO FOOT SECTIONS OF PIPE FROM THE D. BOX SHALL BE SET LEVEL.
- THE SYSTEM SHALL BE STAKED AND THE BENCHMARK SET IN THE FIELD BY THE DESIGN ENGINEER
- ALL UNDERGROUND UTILITIES SHOWN HERE WERE COMPILED ACCORDING TO AVAILABLE RECORD PLANS FROM VARIOUS UTILITY COMPANIES AND PUBLIC AGENCIES AND ARE APPROXIMATE ONLY. ACTUAL LOCATIONS MUST BE DETERMINED BEFORE DESIGNING, EXCAVATING, BLASTING, INSTALLING, BACKFILLING, GRADING, OR PAVEMENT RESTORATION OR REPAIR. ALL UTILITY COMPANIES, PUBLIC AND PRIVATE, MUST BE CONTACTED, INCLUDING THOSE IN CONTROL OF UTILITIES. SEE CHAPTER 370, ACTS OF 1963 MASS. WE ASSUME NO RESPONSIBILITY FOR DAMAGES INCURRED AS A RESULT OF UTILITIES OMITTED OR INACCURATELY SHOWN. BEFORE PLANNING FUTURE CONNECTIONS, THE APPROPRIATE UTILITY ENGINEERING DEPARTMENT MUST BE CONSULTED. D.I.G. SAFE TELE. NO.: 1-888-344-7233.
- RUNOFF FROM THE FRONT PORTION OF THE ROOF SHALL BE DIRECTED TO INFILTRATION DRYWELLS.
- ALL SYSTEM COMPONENTS SHALL BE MARKED WITH MAGNETIC MARKING TAPE OR A COMPARABLE MEANS IN ORDER TO BE LOCATED ONCE BURIED.
- ALL DISTURBED SURFACES SHALL BE RESTORED WITH 6" OF LOAM AND SEED.
- SEWER MANHOLES BROUGHT TO FINISH GRADE SHALL BE SECURED TO PREVENT UNAUTHORIZED ACCESS.
- EFFLUENT TEE FILTER SHALL BE INSTALLED IN COMPLIANCE WITH APPROVAL ISSUED AUGUST 11, 1997. ALL SEWER MANHOLES AT FINISHED GRADE SHALL BE SECURED TO PREVENT UNAUTHORIZED ACCESS. COVER SHALL BE PERMANENTLY MARKED "EFFLUENT TEE FILTER".



PLAN VIEW:

RESIDENCE R-2
 GROUNDWATER PROTECTION
 DISTRICT ZONE 4
 SCALE: 1"=20'



INVERT ELEVATIONS:

4" INV. @ DWELLING	= 120.45
4" INV. @ SEPTIC TANK (IN)	= 120.01
4" INV. @ SEPTIC TANK (OUT)	= 119.76
4" INV. @ D.BOX (IN)	= 119.41
4" INV. @ D.BOX (OUT)	= 119.24
AT LEACHING FACILITY:	
PRIMARY:	
CULTEC CHAMBER (SET LEVEL)	
TOP CHAMBER	= 119.41
4" INV. @ BEGIN CHAMBERS	= 118.95
BOTTOM CHAMBERS	= 118.70
RESERVE:	
CULTEC CHAMBER (SET LEVEL)	
TOP CHAMBER	= 118.18
4" INV. @ BEGIN CHAMBERS	= 117.72
BOTTOM CHAMBERS	= 117.47

DESIGN DATA:

DESIGN FLOW:
 4 BR. X 110 GPD/BR = 440 GPD
 NO GARBAGE DISPOSAL ALLOWED

REQUIRED SEPTIC TANK:
 REQUIRED: 580 & 440 GAL = 1,020 GAL
 PROVIDED: 1000 & 500 GAL = 1,500 GAL


REQUIRED SIZE SOIL ABSORPTION SYSTEM: (PRIMARY & RESERVE)
 PT-B = 28 MPI CLASS II SOIL
 440 GPD / 0.33 GPD/S.F. = 1,333.4 S.F.
 SYSTEM NOT DESIGNED FOR GARBAGE GRINDER
 800 S.F. MINIMUM PER ACTON BOH

TYPE AND SIZE OF SOIL ABSORPTION SYSTEM PROVIDED:
 PRIMARY & RESERVE:
 CULTEC CONTACTOR C-4
 EFFECTIVE LEACHING AREA PER L.F. = 1.67 x 4' = 6.67 SF/LF
 200 LF x 6.67 SF/LF = 1,334 SF
 1,334 SF > 1,333.4 SF O.K.

TITLE V CONVENTIONAL SYSTEM

TYPE AND SIZE OF SOIL ABSORPTION SYSTEM PROVIDED:
 5 TRENCHES: 2' W X 2' D X 45' L
 5 TRENCHES X 6 SF/FT X 45 FT = 1,350 SF > 1,333.4 SF O.K.
 ACTION MIN = 800 S.F.
 1,350 SF > 800 SF O.K.

PROFILE: SCALE: 1"=20' H, 1"=4' V.



SEWAGE DISPOSAL PLAN

PREPARED FOR: LEXINGTON HOLDING, LLC
 ADDRESS: 6 OPEN SPACE DRIVE
 SANDWICH, MA 02563
 (508) 740-8411

LOCATION: LOT 5, CONSTITUTION DRIVE
 ACTON, MA 01720

SCALE: AS SHOWN
 DATE: OCTOBER 3, 2013

PREPARED BY:
STAMSKI AND McNARY, INC
 CIVIL ENGINEERS LAND SURVEYORS
 1000 MAIN STREET - ACTON, MA 01720
 (978) 263-8585

