# ROOM FINISH SCHEDULE

| RM. No. | LOCATION | NORTH WALL MAT. | NORTH WALL FIN. | SOUTH WALL MAT. | SOUTH WALL FIN. | EAST WALL MAT. | EAST WALL FIN. | WEST WALL MAT. | WEST WALL FIN. | SOUND INSULA. | FLOOR MAT. | BASE TYPE/MAT | BASE FIN. | WAIN-SCOT | CHAIR RAIL | CEILING MAT | CEILING HT. | CEILING TRIM | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 01 | ENTRY | DOORS | – | DOORS | – | GYP/LRS | PT | DOORS | – | E | VINYL "SLATE" | 3/A10 | PT. | – | 2/A10 | A.T. | 9'-0" | 1/A10 | NOTE C,I |
| 02 | LOBBY | GYP | PT. | GYP. | PT | GYP. | PT | GYP | PT | N,E | VINYL "SLATE" | 3/A10 | PT | – | 2/A10 | A.T. | 9'-0" | 1/A10 | |
| 03 | MAIN LOBBY | GYP | PT. | GYP. | PT | GYP | PT. | GYP | PT | S,E | VINYL "SLATE" | 3/A10 | PT. | – | 2/A10 | A.T. | 9'-0" | 1/A10 | NOTE C |
| 04 | STORAGE | GYP. | PT. | GYP | PT. | GYP | PT. | GYP | PT | N | CONC. | VINYL | – | – | – | GYP/PT. | 8'-0" | – | NOTE I |
| 05 | OPEN OFFICE | GYP | PT. | GYP. | PT. | GYP. | PT. | GYP. | PT. | ALL | CRPT | 3/A10 | PT. | – | – | A.T. | 9'-0" | 1/A10 | |
| 06 | COMPUTER | GYP. | PT | GYP. | PT. | GYP | PT | GYP. | PT. | ALL | VINYL | 3/A10 | PT. | – | – | A.T. | 9'-0" | 1/A10 | |
| 07 | ACCOUNTANT | GYP. | PT | GYP | PT. | GYP | PT. | GYP. | PT. | N,S,E | CRPT | 3/A10 | PT | – | – | A.T. | 9'-0" | 1/A10 | |
| 08 | FIN. DIRECTOR | GYP. | PT. | GYP | PT. | GYP. | PT | GYP. | PT. | N,E | CONC | VINYL | – | – | 2/A10 | GYP/PT. | 9'-0" | 1/A10 | |
| 09 | TOWN CLERK | GYP | PT. | GYP. | PT. | GYP. | PT. | GYP. | PT. | N,E,W | CRPT. | 3/A10 | PT | – | – | A.T. | 9'-0" | 1/A10 | |
| 10 | ASSESSOR | GYP. | PT. | GYP. | PT. | GYP. | PT. | GYP. | PT. | N,E,W | CRPT | 3/A10 | PT | – | – | A.T. | 9'-0" | 1/A10 | |
| 11 | TAX COLLECTOR | GYP | PT. | GYP. | PT. | GYP. | PT. | GYP | PT. | N,E,W | CRPT | 3/A10 | PT | – | – | A.T. | 9'-0" | 1/A10 | |
| 12 | EMERG. GEN. | GYP | – | GYP | – | GYP. | – | GYP. | – | N,W | CONC | – | – | – | – | GYP. | 8'-6" | – | NOTE B |
| 13 | CONF./OFFICE | GYP. | PT. | GYP | PT. | GYP | PT. | GYP | PT | S,W | CRPT. | 3/A10 | PT | – | – | A.T. | 9'-0" | 1/A10 | |
| 14 | CLOSET | GYP. | PT. | GYP | PT | GYP. | PT | GYP. | PT | E | CRPT | VINYL | – | – | – | GYP/PT | 8'-0" | – | NOTE G |
| 15 | UNUSED | | | | | | | | | | | | | | | | | | |
| 16 | UNUSED | | | | | | | | | | | | | | | | | | |
| 17 | UNUSED | | | | | | | | | | | | | | | | | | |
| 18 | STORAGE | GYP | PT | GYP. | PT | GYP. | PT. | GYP. | PT | – | VINYL | VINYL | – | – | – | GYP/PT | 8'-0" | – | NOTE F (3 SIDES) |
| 19 | VAULT | CONC | PT. | CONC | PT. | GYP. | PT. | CONC | PT. | – | VINYL | VINYL | – | – | – | CONC/PT | – | – | STRAP & INSUL. EAST WALL W/ 1½" RIGID INSUL. |
| 20 | ELECTRIC. RM. | GYP | PT. | CONC. | PT. | GYP | PT. | GYP. | PT. | – | CONC | – | – | – | – | GYP/PT | 9'-6"± | – | |
| 21 | SPRINKLER RM. | GYP | PT. | EXISTING | | EXISTING | | GYP | PT | – | CONC | – | – | – | – | EXISTING | | – | |
| 22 | HALL | GYP. | PT. | GYP. | PT. | EXISTING | | GYP. | PT. | W,N. | CONC | – | – | – | – | EXISTING | | – | |
| 23 | UNUSED | | | | | | | | | | | | | | | | | | |
| 24 | HALL | GYP. | PT. | GYP/GRILLE | PT. | GYP | PT. | GYP. | PT. | N | CRPT | 3/A10 | PT. | – | 2/A10 | A.T. | 7'-11" | 1/A10 | |
| 25 | WOMEN | GYP | PT | GYP. | PT | GYP | PT | GYP | PT | ALL | C.T. | C.T. | – | C.T. | – | A.T | 8'-0" | – | |
| 26 | MEN | GYP. | PT | GYP | PT. | GYP | PT | GYP. | PT. | ALL | C.T | C.T. | – | C.T. | – | A.T | 8'-0" | – | |
| 27 | REPROGRAPHICS | GYP | PT | GYP | PT. | GYP. | PT. | GYP | PT. | ALL | VINYL | 3/A10 | PT. | – | – | A.T. | 8'-0" | – | |
| 28 | VESTIBULE | GYP. | PT. | GYP | PT | GYP. | PT. | GYP | PT | E,W | CRPT | 3/A10 | PT. | – | 2/A10 | A.T. | 8'-0" | 1/A10 | |
| 29 | HALL | GYP. | PT. | GYP | PT. | GYP. | PT. | GYP | PT. | N,S | CRPT. | 3/A10 | PT. | – | 2/A10 | A.T. | 7'-11" | 1/A10 | |
| 30 | MECHANICAL | GYP. | PT. | GYP | PT. | GYP. | PT. | GYP | PT | ALL | CONC | – | – | – | – | GYP/PT | 9'-6" | – | NOTE B |
| 31 | ELEV. MECH. | GYP | PT | GYP | PT. | GYP. | PT. | GYP | PT | S,W | CONC | – | – | – | – | GYP/PT. | 8'-0" | – | NOTE B |
| 32 | JANITOR | GYP | PT | GYP | PT | GYP. | PT. | GYP | PT. | N,S | CONC | – | – | – | – | GYP/PT | 8'-0" | – | |
| 33 | HANDICAP TOIL. | GYP | PT | GYP | PT | GYP | PT | GYP | PT. | ALL | C.T. | C.T. | – | C.T. | – | A.T. | 8'-0" | – | |
| 34 | BLDG. DEPT. | GYP | PT | GYP | PT | GYP | PT | GYP | PT. | N,S,E | CRPT. | 3/A10 | PT. | – | – | A.T. | 9'-0 | 1/A10 | |
| 35 | BLDG. COMMISS. | GYP. | PT | GYP | PT. | GYP | PT. | GYP | PT | S,E | CRPT | 3/A10 | PT | GYP/PT | 2/A10 | A.T. | 9'-0 | 1/A10 | |
| 36 | ASS'T. | GYP | PT | GYP | PT | GYP. | PT. | GYP | PT. | S,E,W | CRPT | 3/A10 | PT. | – | – | A.T. | 9'-0" | 1/A10 | |
| 37 | BRD. OF HEALTH | GYP | PT | GYP. | PT. | GYP | PT. | GYP | PT | ALL | CRPT | 3/A10 | PT | – | – | A.T. | 9'-0" | 1/A10 | |
| 38 | DIRECTOR | GYP. | PT | GYP | PT | GYP. | PT. | GYP | PT. | S,E,W | CRPT. | 3/A10 | PT. | – | – | A.T. | 9'-0" | 1/A10 | |
| 39 | ASSIST. | GYP | PT | GYP | PT. | GYP | PT | GYP | PT. | S,E,W | CRPT. | 3/A10 | PT. | – | – | A.T. | 9'-0" | 1/A10 | |
| 40 | PLAN DEPT. | GYP | PT. | GYP | PT | GYP. | PT | GYP. | PT | ALL | CRPT. | 3/A10 | PT | – | – | A.T. | 9'-0" | 1/A10 | |
| 41 | PLANNER | GYP | PT | GYP | PT | GYP | PT | GYP | PT | S,E,W | CRPT. | 3/A10 | PT. | – | – | A.T | 9'-0" | 1/A10 | |
| 42 | ENGINEER DEPT. | GYP | PT | GYP | PT | GYP | PT | GYP | PT. | S,W | CRPT. | 3/A10 | PT | – | – | A.T | 9'-0" | 1/A10 | |
| 43 | TOWN ENGINEER | GYP | PT | GYP | PT | GYP | PT. | GYP. | PT. | S,W | CRPT. | 3/A10 | PT. | – | – | A.T | 9'-0" | 1/A10 | |
| 44 | PLAN & PRINT | GYP. | PT. | GYP | PT | GYP. | PT. | GYP. | PT. | – | VINYL | VINYL | PT. | – | – | A.T. | 9'-0" | – | |
| 45 | EXIST. VAULT | CLEAN & | PAINT | EXISTING | | WALLS & | | FLOOR & | | CEILING | | | | – | – | – | – | – | RETAIN MTL. SHELVING |
| 46 | CONFERENCE | GYP | PT. | GYP | PT. | GYP | PT | GYP. | PT. | ALL | CRPT. | 3/A10 | PT. | – | 2/A10 | A.T. | 8'-0" | 1/A10 | |
| 47 | UNUSED | | | | | | | | | | | | | | | | | | |
| 48 | COUNTER AREA | GRILLE & COUNTER | – | – | – | GYP | PT | GYP | PT. | W | CRPT | 3/A10 | PT. | – | – | A.T. | 7'-11" | – | SEE DETAILS SHEET A13 |
| 49 | REPRO. CLOSET | GYP | PT | GYP | PT | GYP | PT | GYP | PT | N,W | VINYL | VINYL | – | – | – | GYP/PT | 8'-0 | – | |
| 101 | LOBBY | PATCH & REPAIR WALLS AT RADIATOR REMOVAL & SPOT PAINT | | | | | | | | — | NEW VINYL | EXIST. WD. | | | | | | – | PROTECT ALL FINISHES TO REMAIN DURING CONST. |
| 102 | JANITOR | PATCH WALLS & WAINSCOT AT TOIL. FTN. & FIXTURE REMOVAL & PAINT WALLS | | | | | | | | – | PATCH EX. C.T. | – | – | PATCH EXIST. | – | EXIST/PT. | 9'-6"± | – | REMOVE EXIST. URINAL FTN. & URINAL |
| 103 | CLOSET | GYP. | PT. | EXIST. | PATCH & PT | GYP | PT | GYP. | PT | E | CRPT | VINYL | – | – | – | GYP. | 8'-0" | – | NOTE F |
| 104 | RECEPTION | EXIST | PATCH & PT | EXIST. | PATCH & PT | EXIST. & NEW | PATCH & PT. | EXIST. & NEW | PATCH & PT. | – | CRPT | EXIST/NEW | PT. | – | EXIST/NEW | EXIST/PATCH & PT | 10'-8"± | EXIST/4/A10 | NOTES D, E |
| 105 | CLOSET | EXIST. | PATCH & PT | EXIST. | PATCH & PT | EXIST. | PATCH & PT. | EXIST. | PATCH & PT | – | CRPT. | EXIST. | – | – | – | GYP/PT. | 8'-0" | – | NOTE G |
| 106 | CLOSET | EXIST. | PATCH & PT | EXIST. | PATCH & PT. | EXIST. | PATCH & PT | EXIST. | PATCH & PT. | – | CRPT. | EXIST. | – | – | – | GYP/PT. | 8'-0" | – | NOTE G |
| 107 | SELECTMEN SEC'Y | EXIST. | PATCH & PT | EXIST | PATCH & PT. | EXIST. | PATCH & PT. | EXIST | PATCH & PT | – | CRPT | EXIST/NEW | PT. | – | EXIST. PATCH/PT | (SEE NOTE "H") | | | NOTE H. REMOVE TILES FROM WEST WALL & REPAIR |
| 108 | UNUSED | | | | | | | | | | | | | | | | | | |
| 109 | SELECTMEN (2) | REMOVE EXISTING WALL COVERING AND WALL MOULDINGS. PAINT ALL WALLS | | | | | | | | – | CRPT | EXIST. | PT. | – | — | EXIST./PATCH & PT. | 10'-8"± | EXIST./PT. | |
| 110 | CLOSET-T.M.A. | NO WORK EXCEPT PAINT | | | | | | | | | | | | | | | | | |
| 111 | TOWN MANAGER | EXIST. | PATCH & PT. | EXIST. | PATCH & PT. | EXIST. | PATCH & PT. | EXIST | PATCH & PT. | – | CRPT. | EXIST/NEW | PT. | GYP/PT | EXIST/PATCH | EXIST/PATCH & PT | 10'-8"± | EXIST/4/A10 | NOTES D, E |

# ROOM FINISH SCHEDULE

| RM. No. | LOCATION | NORTH WALL MAT. | NORTH WALL FIN. | SOUTH WALL MAT. | SOUTH WALL FIN. | EAST WALL MAT. | EAST WALL FIN. | WEST WALL MAT. | WEST WALL FIN. | SOUND INSULA. | FLOOR MAT. | BASE MAT. | BASE FIN. | WAIN-SCOT | CHAIR RAIL | CEILING MAT. | CEILING HT. | CEILING TRIM | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 112 | CLOSET | GYP. | PT. | EXIST. | PATCH & PT. | EXIST | PATCH & PT. | EXIST. | PATCH & PT. | N | CRPT | VINYL | – | – | – | GYP/PT | 8'-0" | – | NOTE F |
| 113 | T.M. SEC'Y. | GYP. | PT. | EXIST | PATCH & PT. | EXIST | PATCH & PT. | GYP. | PT. | N,W | CRPT | WD | PT | – | EXIST/NEW | EXIST/PATCH & PT | 10'-8"± | 4/A10 | NOTES D, E |
| 114 | T.M. ASSISTANT | GYP. | PT. | EXIST. | PATCH & PT. | GYP. | PT. | EXIST/GYP. | PATCH & PT. | N,E,W | CRPT. | WD | PT | – | EXIST. | EXIST/PATCH & PT | 10'-8"± | 4/A10 | NOTE E. |
| 115 | HALL | GYP. | PT. | GYP. | PT. | – | – | GYP | PT. | N,S. | CRPT | NEW TO MATCH | PT. | – | NEW TO MATCH | A.T. | 8'-0" | 1/A10 | NOTES D, E |
| 116 | HALL | GYP. | PT. | GYP | PT | GYP | PT | GYP. | PT | ALL | CRPT | 3/A10 | PT | – | 2/A10 | A.T. | 8'-0" | 1/A10 | NOTE I |
| 117 | MUNICIPAL PROP. | GYP. | PT. | GYP. | PT. | GYP. | PT | GYP | PT | N,E,W | CRPT. | 3/A10 | PT. | – | – | A.T | 9'-0" | 1/A10 | |
| 118 | MUN. PROP. CLERK | GYP | PT | GYP | PT | GYP | PT | GYP | PT. | N,E | CRPT. | 3/A10 | PT. | – | – | A.T. | 9'-0" | 1/A10 | |
| 119 | CONSERV. ADMIN. | GYP | PT. | GYP | PT | GYP | PT | GYP. | PT | N,E,S | CRPT. | 3/A10 | PT. | – | – | A.T. | 9'-0" | 1/A10 | |
| 120 | D.P.W. DIR. | GYP. | PT | GYP | PT. | GYP. | PT. | GYP. | PT. | S,E | CRPT | 3/A10 | PT | – | – | A.T. | 9'-0" | 1/A10 | |
| 121 | CONFERENCE | GYP. | PT. | GYP. | PT. | GYP. | PT. | GYP. | PT. | S,W | CRPT. | 3/A10 | PT. | – | – | A.T. | 9'-0" | 1/A10 | |
| 122 | CLOSET | NO WORK EXCEPT PAINT | | | | | | | | | | | | | | | | | |
| 123 | CLOSET | NO WORK EXCEPT PAINT | | | | | | | | | | | | | | | | | |
| 124 | CLOSET | NO WORK EXCEPT PAINT | | | | | | | | | | | | | | | | | |
| 125 | LOUNGE | EXIST | PATCH & PT. | EXIST | PATCH & PT. | EXIST./NEW | PATCH & PT | EXIST | PATCH & PT. | S | CRPT. | EX. WD | PT | – | EXIST/PT | EXIST/PATCH & PT | EXIST | EXIST/PT | NOTE E |
| 126 | CONFERENCE | EXIST. | PATCH & PT. | EXIST | PATCH & PT. | GYP | PT. | EXIST./NEW | PATCH & PT | E | CRPT. | EX. WD | PT. | – | EXIST/PT | EXIST/PATCH & PT | 10'-8"± | EXIST & 4/A10 | NOTE E. EXIST. CORNICE TO REMAIN ON N,S & W WALLS |
| 127 | (2) SELECTMEN | EXIST | PATCH & PT | EXIST | PATCH & PT. | EXIST./NEW | PATCH & PT. | GYP. | PT. | E,W | CRPT. | EX. WD | PT. | – | EXIST/PT | EXIST/PATCH & PT | 10'-8"± | EXIST & 4/A10 | NOTE E. EXIST. CORNICE TO REMAIN ON S & E WALLS |
| 128 | COPY CENTER | EXIST | PATCH & PT. | EXIST | PATCH & PT. | EXIST. | PATCH & PT. | EXIST./NEW | PATCH & PT. | W | CRPT. | EX. WD | PT | – | EXIST/PT. | EXIST/PATCH & PT | EXIST. | EXIST/PT | NOTE E. |
| 129 | EXIST. VAULT | CLEAN & | PAINT | EXISTING | | WALLS & | | | | FLOOR & | | CEILING | | – | – | – | – | – | RETAIN MTL. SHELVING. |
| 130 | CLOSET-RECEIP. | EXIST | PATCH & PT | GYP | PT | EXIST | PATCH & PT. | GYP | PT | W | CRPT | VINYL | – | – | – | GYP/PT | 8'-0" | – | NOTE F |
| 131 | CLOSET-RECEP. | GYP | PT | GYP | PT | EXIST. | PATCH & PT. | GYP | PT | W | CRPT | VINYL | – | – | – | GYP/PT | 8'-0" | – | NOTE F |
| 132 | H/C WOMEN | EXIST | PATCH & PT | GYP | PT. | GYP. | PT. | GYP | PT | ALL | C.T. | C.T. | – | C.T. | – | A.T. | 8'-0" | – | |
| 133 | H/C MEN | EXIST. | PATCH & PT | GYP | PT | GYP | PT | GYP | PT. | ALL | C.T. | C.T. | – | C.T. | – | A.T | 8'-0" | – | |
| 201 | LOBBY | NO | WORK | | | | | | | | | | | | | | | | |
| 202 | EXIST. WOMEN RM. | NO | WORK | | | | | | | | | | | | | | | | |
| 203 | A.V. STORAGE | NO | WORK | | | | | | | | | | | | | | | | |
| 204 | MEETING HALL | NO | WORK | | | | | | | | | | | | | | | | |
| 204A | CONFERENCE | NO | WORK | | | | | | | | | | | | | | | | |
| 204B | CONFERENCE | NO | WORK | | | | | | | | | | | | | | | | |
| 205 | LOBBY | GYP. | PT | GYP | PT. | GYP. | PT. | GYP. | PT | W | CRPT | 3/A10 | PT | – | 2/A10 | A.T. | 8'-9" | 1/A10 | |
| 206 | HALL | GYP. | PT | GYP. | PT. | GYP | PT. | GYP. | PT | ALL | CRPT | 3/A10 | PT. | – | 2/A10 | A.T. | 8'-0" | 1/A10 | NOTE I |
| 207 | SEC'Y./BOOKK. | GYP. | PT | GYP | PT. | GYP. | PT. | GYP. | PT | N,E | CRPT. | 3/A10 | PT. | – | – | A.T. | 8'-9" | 1/A10 | |
| 208 | SUPERVISOR | GYP. | PT. | GYP | PT | GYP. | PT. | GYP. | PT | N,E,W | CRPT. | 3/A10 | PT. | – | – | A.T. | 8'-9" | 1/A10 | |
| 209 | NURSES | GYP | PT. | GYP | PT | GYP. | PT | GYP. | PT | N,E,S | CRPT. | 3/A10 | PT. | – | – | A.T | 8'-9" | 1/A10 | |
| 210 | CONFERENCE | GYP. | PT | GYP. | PT | GYP | PT. | GYP. | PT | S,E | VINYL | 3/A10 | PT. | – | – | A.T. | 8'-9" | 1/A10 | |
| 211 | EXAM. | GYP. | VINYL | GYP | VINYL | GYP. | VINYL | GYP | VINYL | S,W | VINYL | 3/A10 | PT. | – | – | A.T. | 8'-9" | 1/A10 | |
| 212 | TOILET | GYP | PT | GYP. | PT. | GYP. | PT. | GYP. | PT | ALL | VINYL | 3/A10 | PT. | – | – | A.T | 8'-9" | – | |
| 213 | HALL | GYP | PT | GYP | PT | GYP | PT | GYP | PT. | S,E,W | VINYL | 3/A10 | PT | – | – | A.T. | 8'-9" | 1/A10 | |
| 214 | ELECTRICAL CL. | GYP | PT | GYP | PT | GYP | PT. | GYP | PT. | S | CRPT | VINYL | – | – | – | GYP/PT | 8'-0" | – | |
| 301 | STORAGE BALC. | NO | WORK. | | | | | | | | | | | | | | | | |
| 302 | STORAGE | GYP | PT | GYP. | PT. | GYP | PT. | GYP. | PT. | – | PLYWD. | VINYL | – | – | – | A.T | 7'-5" | – | |
| 303 | STORAGE | GYP. | PT. | GYP | PT. | GYP | PT. | GYP | PT | – | PLYWD. | VINYL | – | – | – | A.T | 7'-5" | – | NOTE I |
| 304 | STORAGE | GYP. | PT. | GYP. | PT. | GYP. | PT. | GYP | PT. | – | PLYWD. | VINYL | – | – | – | A.T. | 7'-5" | – | |
| 401 | EXIST'G ATTIC | NO | WORK | EXCEPT | | AS NOTED ON DRAWING A2 | | | | | | | | | | | | | |
| 402 | CLOCK RM. | NO | WORK | | | | | | | | | | | | | | | | |
| 403 | BALCONY | GYP | PT. | GYP. | PT. | GYP | PT. | GYP | PT. | – | PLYWD. | VINYL | – | – | – | GYP/PT. | 7'-0" | – | NOTE I |
| A | STAIR | GYP | PT. | DOORS/GYP. | PT | GYP | PT | GYP | PT. | N,E,W | CRPT./WOOD | WOOD | PT | – | – | GYP/PT | – | – | NOTES C, I & J. SEE DETAILS ON SHEET A16 |
| B | STAIR | GYP/EXIST. | PT | GYP | PT | GYP | PT | GYP | PT. | N,W | CRPT/VINYL | | PT | – | – | GYP/PT | – | – | NOTE C. SEE DETAILS ON SHEET A15. CARPET LANDINGS VINYL TREADS & RISERS |
| C | STAIR | NO | WORK | | | | | | | | | | | | | | | | |
| D | STAIR | NO | WORK | | | | | | | | | | | | | | | | |
| E | STAIR | NO | WORK | | | | | | | | | | | | | | | | |
| F | STAIR | NO | WORK | EXCEPT | | REPAIR | | | | LOOSE | | TREADS | | | | | | | |
| G | STAIR | NO | WORK | | | | | | | | | | | | | | | | |

## FINISH SCHEDULE NOTES

A. SOUND INSULATION: INSULATE ALL NEW INTERIOR WALLS FLOOR TO CEILING FOR SOUND AS NOTED NORTH, SOUTH, EAST AND WEST.

B. NEW WALLS AND CEILING SHALL BE 2 HOUR RATED: 2 LAYERS 5/8" FIRECODE GYPSUM BOARD BOTH SIDES.

C. NEW WALLS AND CEILING SHALL BE 1 HOUR RATED: 1 LAYER 5/8" FIRECODE GYPSUM BOARD BOTH SIDES.

D. PATCH/MATCH EXISTING WOOD CHAIR RAIL TRIM AT 2'-8½"± ABOVE FLOOR, PAINT FINISH.

E. PATCH/MATCH EXISTING WOOD BASEBOARD, PAINT.

F. FIVE (5) NEW WOOD SHELVES 12" WIDE ON ADJUSTABLE METAL TRACK WITH BRACKETS.

G. TYPICAL 1⅜" DIAMETER WOOD ROD ON METAL BRACKETS WITH FIXED 12" WIDE WOOD SHELF AT 5'-6" ABOVE FLOOR.

H. IN ROOM 107, REMOVE EXISTING SUSPENDED ACOUSTIC TILE CEILING. REPAIR AND REPAINT EXISTING TIN CEILING ABOVE. IF EXISTING TIN CEILING IS BEYOND REPAIR ACCORDING TO ARCHITECTS JUDGEMENT OR DOES NOT EXIST, INSTALL A NEW 5/8" GYPSUM BOARD CEILING ON 3/4" STRAPPING AT UNDERSIDE OF FLOOR JOISTS WITH NEW CORNICE PER DETAIL 4/A10. PAINT FINISH.

I. AT WALLS COMMON IN PART OR WHOLE WITH ELEVATOR SHAFT WALLS, FINISH ENTIRE WALL WITH 2 LAYERS 5/8" FIRECODE GYPSUM BOARD BOTH SIDES. ELEVATOR SHAFT SHALL HAVE 2 LAYERS 5/8" FIRECODE GYPSUM BOARD BOTH SIDES.

J. STAIN HANDRAIL & SUBRAIL TO DUPLICATE MAHOGANY, WITH SEMI-GLOSS POLYURETHANE TOP COAT. FINISH PAINT ALL OTHER COMPONENTS INCLUDING RISERS. FINISH TREADS & LANDINGS WITH SEMI-GLOSS POLYURETHANE.

Additions and Renovations to
THE ACTON TOWN HALL
Acton, Massachusetts

title: ROOM FINISH SCHEDULE

ROBERT G. NEILEY ARCHITECTS
286 Congress Street, Boston MA 02210

drawn by JPS | job 8523 | scale – | date 4-6-87

drawing A7