

Table 1: Wetland Resource Area Impacts - Acton - Assabet River Rail Trail

ROW STA No. #	Brook Name	Wetland Resource Area Impacts							Comments
		BVW		Bank(If)	BLSF Sq. ft	BLSF c.f.	LUW/other Waters of the U.S.		
		Perm. (sf)	Temp. (sf)				Perm. (sf)	Temp. (sf)	
122+00	Railroad drainage swale							13.11	Temporary LUW impacts to be restored at impact location.
125 + 25 RT	Pratts Brook		38.22						Temporary BVW impacts to be restored at impact location.
126 + 25 RT	Pratts Brook		16.23						Temporary BVW impacts to be restored at impact location.
134+75 to 137+75	Stormwater Feature BVWs		2798.78						Limited Project - impacts associated with boardwalk over detention basins. Temporary BVW impacts to be restored in place.
138+00 to 140+43	Shrub Swamp BVW		6276.18						Limited Project - impacts associated with boardwalk. Temporary BVW impacts to be restored in place.
152 + 50	Railroad drainage swale						77.24		Permanent impacts to LUW will meet all performance standards detailed at 310 CMR 10.56(4).
152+75	Railroad drainage swale			34.20				260.53	Bank resotration proposed at impact location. Temporary LUW impacts to be restored at impact location.
153 + 25 to 153+50	Railroad drainage swale			75.00			157.16		Bank restoration proposed at impact location. Permanent impacts to LUW will meet all performance standards detailed at 310 CMR 10.56(4).

Table 1: Wetland Resource Area Impacts - Acton - Assabet River Rail Trail

ROW STA No. #	Brook Name	Wetland Resource Area Impacts							Comments
		BVW		Bank(If)	BLSF Sq. ft	BLSF c.f.	LUW/other Waters of the U.S.		
		Perm. (sf)	Temp. (sf)				Perm. (sf)	Temp. (sf)	
154+50 to 155+50	Railroad drainage swale			20.60			19.64	168.68	Bank restoration proposed at impact location. Temporary LUW impacts to be restored at impact location. Permanent impacts to LUW will meet all performance standards detailed at 310 CMR 10.56(4).
169 + 50 to 170 + 00	Mill Pond							323.50	Temporary LUW impacts associated with removal of existing bridge pilings.
TOTAL		0.00	9129.41	129.80	0.00	0.00	254.04	765.82	

Notes: #####

#####